

Annex 4

**Tender reference no:** FCA-2016P4

**Title: Construction of Semi-Permanent School Buildings in Gumuruk (GPAA)**

**Contracting Authority:** Finn Church Aid (FCA) – South Sudan

**Deadline for submission of bids:** 30/09/2016

### INVITATION TO BID

FCA is launching a “Tender”– sealed bid” and invites suppliers interested in construction of semi-permanent school buildings in Gumuruk.

ITEM / LOT	DESCRIPTION	QUANTITY
1.	• Construction of semi-permanent school buildings in Gumuruk and Pibor- GPAA (Including construction material, labour and transport cost)	8 Blocks

#### ITEM/LOT:

1. Construction of 8 Blocks Semi -Permanent School Building (4 Blocks in Pibor and 4 Blocks in Gumuruk)

#### Bill of Quantities

S/N	Description of Work	Quantity	Unit	Rate in USD	Total Amount	Remarks
1	Earthwork in excavation in ordinary soils	16.09	Cu.m			
2	Flat dry brick soiling on flat in foundation and floor including sand filling in joints	29.92	Sq.m			
3	P.C.C. 1:2:4 in Foundation	1.57	Cu.m			
4	PCC 1:2:4 in floor	10:30	Cu.m			
5	M.S. black pipe roof truss with primer painting with all necessary M.S. bed plates, shoe angles anchor bolts leas	1582.68	kg			
6	Good quality local chimnery made Brickwork in 1:4 C/S mortar up to ground floor	20.67	Cu.m			
7	230mm thick hollow concrete block wall	10.11	Cu.m			
8	12.5mm thick 1:4 cement sand plaster	100.75	Sqm			
9	0.50mm colour CGI sheet roofing	110.70	Sq.m			
10	Covering gable section with 50mm plane GI sheet	11.25	Sq.m			
11	Redge cover 0.45mm thick colour sheet	15.00	R.m			
12	Supplying and Fitting Aluminium Panel sliding window section	12.96	Sq.m			

	88*38.1*1.3mm without ventilator					
13	Aluminium casement door section (101x45x1.5)mm	8.61	Sq.m			
14	0.50mm thick plane sheet 150mm width gutter work	30.00	R.m.			
15	110mm thick PVC pipe 6kg/cm <sup>2</sup>	10.00	R.m			
16	Earth filling 150mm thick layer, watering and raming including supply of filling materials with 6km distance	39.19	Cu.m			
17	Site clearance before & after	1.00	Job			
18	Supplying and fixing 50mm thick prefabricated V- PANEL wall with necessary accessories	45.0	Sq.m			
19	Painting 2 coata pex paint (weather coat) with primer	105.62	Sq.m			
20	Painting 2 coat plastic emulsion paint with primer	87.49	Sq.m			
21	19mm thick plywood from work Shutting, centering with Approved Materials for FOUNDATION	1.22	Sq.m			
Grand Total						

Bidding will be conducted through open tender procedure.

1. The tender is for a humanitarian project (11696) in GPAA, Pibor and Gumuruk an intervention supported by Finland Government.
2. All logistics handling, construction material and transport of material from Juba to Gumuruk and Pibor will be under the responsibility of the successful bidder.
3. Please note, the bid prices shall be quoted in USD only.
4. All bids (sealed), in English language only must be delivered to the office mentioned below by 4:00PM, 30<sup>th</sup> September, 2016 and signed for indicating date and time of delivery. Late bids will not be considered.
5. Applicants with questions regarding this tender should be sent in writing to email [admin.ssuco@kua.fi](mailto:admin.ssuco@kua.fi) or in a sealed envelope to address mentioned below up to 16 hours, 22<sup>nd</sup> September, 2016.
6. Tenderers will be notified on the date and time for opening of the bid documents.
7. Bidders may obtain a complete set of bidding documents in English at no cost from the office mentioned below.

**NOTE:**

1. **Material transport costs from Juba to Gumuruk should be detailed separately**
2. **For more information about the plan of the school block, contact our offices.**
3. **Tender documents are available and can be collected at the FCA offices**

Finn Church Aid (FCA)  
Juba Nabari Area, Bilpham Road  
Juba - South Sudan