



BILL OF QUANTITY FOR REHABILITATION OF 08 DEFUNCT BOREHOLES:

Project: SSHF Q2

Location: Yei town and surroundings

S/no	Item description	Quantity	Unit	Unit cost- USD	Amount - USD
01	Allow for dismantling Head assembly MK II and provide new ones including dismantling and fixing	02	Pieces		
03	Allow for dismantling water tank assembly , hence provide and allow for fixing new ones	01	pieces		
05	Allow for dismantling damaged G.I.Pipes 1 1/4" – 3m complete with 12 mm connecting rods , hence provide and allow for fixing new ones in place	103	Set		
07	Allow for dismantling damaged cylinder assembly MK III , hence provide and allow for fixing new ones in place	01	Pieces		
08	Allow for dismantling damaged cylinder assembly MK II , hence provide and allow for fixing new ones in place	08	Pieces		
09	Allow for dismantling damaged aprons , hence provide and allow for major repair of complete apron including drainage channels , allow for provision of cement , aggregate and sand	6.5	M ³		
10	Allow for dismantling portions of damaged aprons , hence provide and allow for minor repair of apron	1.5	M ³		

	including drainage channels , allow for provision of cement , aggregate and sand				
11	Visibility (sticker 20cm x 17 cm) 08 with IRW logo and 08 with SSHF logo	16	pieces		