



GENERAL NOTE

1. All dimensions are shown in mm unless otherwise specified
2. Drawings are not to scale only figure dimensions to be used
3. Contractor must check and verify all dimensions on site before commencement of any work.

STRUCTURAL DETAILS

1. 25mm cement screed mix 1:3
2. 100mm oversite concrete mix 1:3:6
3. 300mm hardcore filling on well compacted ground
4. 50 years guarantee anti-termite treatment under the ground

CIVIL.

1. All soil on cut embankments to be stabilized. the slope not to exceed the natural angle of repose.
2. All black cotton soil to be removed from below the building and paved surfaces.
3. The depth of the foundation to be determined by S.E approval
4. All walls thickness to be reinforced with hoop iron at every alternate course of three.

MECHANICAL.

1. All plumbing and drainage to comply with municipal council specification.

GROUND PLAN FOR NUTRITION SITE IN KAPOETA MISSION HOSPITAL