



Tongpiny, Juba Nabari,
 Along Catholic University Road
 Tel: 0922606095,
 Email: info@gliAfrica.org

BILL OF QUANTITY FOR REHABILITATION OF 01 BLOCK OF VIP LATRINE

Project: " IRRH

Project location: Ramogi PHCU – Kajo Keji County

Ref Number	Item description	Quantity	Unit	Unit cost -USD	Amount - USD
01	<i>Provide and allow for rehabilitation of complete roof structure of the latrine block: roof cover, timber Rafters, purlins, fascia boards. :</i>				
	- G.C.I. Sheet roof coverings (28 gauge , IT 4)	07	Pieces		
	- Sawn Timber 2"x4" – Rafters and wall plates	6	Pieces		
	- Sawn timbers 2"x3" - purlins	6	Pieces		
	- 1"x8" wroth soft wood timber in (fascia boards) pre painted white .	20	meters		
	- Roofing nails complete with plastic washer	01	Kgm		
	- Pin nails assorted	2.5	Kgm		
	- Nails 2"	2	Kgs		
	- Nails 3"	2	Kgs		
	- Nails 4 "	5	Kgs		
	- Nails 5"	2	Kgs		
	- 15 cm long mild steel wall cramp	06	pieces		
	Sub total (1) carried to summery				
02	<i>Provide and allow for carpentry work and fixing in place of complete wooden doors. (2"x4" well treated timber work in door frames complete with 6 no , 15 cm long fish tailed wall cramps firmly nailed on the door frames . 0.90m x1,90m wooden door shutter with two diagonal ties fabricated from 2"x3" well treated timber all around and one divider in the middle , ½"x6" well treated timbers , legged in panels well</i>				

	<i>nailed on the frames, complete with 6" T-hinges, barrel bolt locks inside and staple and hasp for external locks complete with padlocks.</i>			
	- Complete metallic doors 1.90m height x 0.90m width	02	Pieces	
	Sub total (2) carried to summery			
03	<i>Provide and allow for 0.25m thick brick work, 1.60m height and 5.00m long in 1:4 cement to sand mortar in curtain wall in front of the toilet block at 1.10m distance from the front wall.</i>			
	- Brick work	9.00	M ²	
	- Plastering work 1:3 cement to sand mortar well finished	18.00	M ²	
	Sub total (3) carried to summery			
04	<i>Provide and allow for repair work on dilapidated floors and walls of latrine block, 1:3 mortar mix in screeds on floor finished smooth in cement grout. ditto but, repair work on cracks on walls, splash apron and around door openings.</i>			
	- Cement	6	Bags	
	- Sand	03	Cubic meter	
	Sub total (4) carried to summery			
05	<i>Provide and apply at least two coats of selected paints on both external and internal wall surfaces. Ditto but :</i>			
	- Paints on walls, 10 cm height skirting both for external and internal surfaces.	48.40	M ²	
	Sub total(5) carried to summery			
	Grand total = Subtotal(1)+(2)+(3)+(4)+(5)			

Note:

Ensure all costs quoted on this BOQ includes cost of materials, labour, transportation, equipment, storage and any related costs.