



# LOT 2



## TENDER AVERT CONSTRUCTION OF WOMEN & GIRLS FRIENDLY SPACE 20M\*10M IN THORNOR - LEER UNITY STATE

Name of Company:		Phone number:	
Address:			
PIN number or equivalent:			
Email address			

S/No	PARTICULARS	UNIT	QUANTITY	RATE USD	AMOUNT USD
1a	Mobilization of equipment, tools, materials, and Labor	Item	1		
2a	Clear the site cut bushes and grab uproots to prepare for construction	Item	1		
2b	Excavation over site 150mm deep to repair to soil	M3	1		
2c	Excavation foundation trench starting from tripped level for trip footing	M3	20		
2d	Filling and ramping around foundation trip with gravel or other equal and	M3	48		
2f	Carry away surplus excavated material to deposit	M3	15		
2g	Anti-termite treatment to stabilize compacted floor area, filling and top of foundation wall collection for earth work	2M	68		
3a	Concrete class 25/20/1/2/4 in trip footing	3M	2		
3b	100mm thick floor slab	M3	6		
3c	100mm thick for pavement and ramp	3M	5		
3d	200x200mm ring beam	3M	2		
4a	25mm thick saw cypress form work to side and soft fit of beams	M	42		
4b	Edges of floor slab height not exceeding 150mm high	M	68		

5b	R8 mild steel reinforcement bar	PCS	80		
5c	Y12 high yield reinforcement bar	PCS	80		
5d	Y10 high yield reinforcement bar	PCS	80		
5e	Binding Wire Rolls	Roll	6		
5f	Hoop Iron	Roll	8		
7a	225mm wide horizontal bituminous damp proof course laid on screed	M2	7		
7b	Horizontal damp proof membrane 1000- gauge polythene laid on compacted ground floor.	M2	68		
8a	Timbers 6x2	PCS	150		
8b	Timbers 4x2	PCS	200		
8c	Timbers 3x2	PCS	250		
8e	Roofing guage (28G Pre-painted Iron Sheet)	PCS	200		
8f	Ridge Caps	PCS	40		
8g	Facial boards	PCS	20		
9a	Steel casement windows to fit structural opening size 150x150cm high comprising of steel frames including all iron monger and hardware	No	4		
9b	Steel casement Door to fit structural opening size 100x240 high comprising of steel frames including all iron monger and hardware	No	2		
10a	25mm thick cement sand mix (1:3) plaster smooth finish with stell float internal with lime	M <sub>2</sub>	11		
10b	25mm thick cement sand mix (1:4) plaster smooth finish with stell float external wall	M <sub>2</sub>	11		
10c	Supply and place 40mm thick cement sand mix (1:3) screed laid horizontal on the floor slab surface finished with shurry steel float	M <sub>2</sub>	80		
11a	Common nails	Kg	100		
11b	Roofing nails	Kg	150		
11c	Wire Mesh 8.6 x 26 M	Pcs	30		
11d	Boards 4x8 6mm (ALL FORM WORKS)	Pcs	70		
12a	Cement	Bags	100		
12b	Paint 20 Liters	Buckets	18		
13	Labour	Lumpsum			

**TABLE 2: Offer to Comply with Other Conditions and Related Requirements**

Other Information pertaining to our Tender are as follows:	Your Responses (Tick appropriately)		
	Yes, we will comply	No, we cannot	If you cannot
Partial Bidding: Not acceptable within a lot.			
Currency of Quotation: US\$			
Payment terms: HRSS South Sudan operates on a			
Delivery Lead Time: 21 days upon purchase			
<b>Delivery terms:</b>			
<b>Validity of Quotation:</b> (90 days)			
1 Year warranty on services and equipment parts of			
Liquidated damages: 0.5% of contract for every day of			
<b>ARTICLE : PERFORMANCE SECURITY.</b> Required in an amount			
For the supplier			
Name:			
Title:			
Signature and			
Date:			