

Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

**Plot No. 246, Block 3k 2nd Class Residential,  
Tonging Behind Indian Embassy,  
Central Equatoria State,  
Juba South Sudan**

**3<sup>rd</sup> November 2023**

Request for Quotations 2<sup>nd</sup> Round  
RFQ\_JUB\_2023\_0207

Rehabilitation of Water System Infrastructure at three (3) Primary Schools Gumbo Basic Primary School; Rajaf West primary School and Kapuri Primary School

- A. Annex 1: Specification of Bidding
- B. Annex 2: Bill of Quantity

We look forward to receiving your quotations by or before the **submission deadline on 7<sup>th</sup> November 2023 at or before 12:00 pm** via E-mail to: [mb.procurement-juba@malteser-international.org](mailto:mb.procurement-juba@malteser-international.org)

Please write in the Subject line of your email with quotation: **RFQ\_JUB\_2022\_0207** for rehabilitation of Water System Infrastructure at three (3) three Schools Gumbo Basic Primary School; Rajaf West primary School and Kapuri Primary School in Juba, South Sudan, Juba.

Thank you for your cooperation.

Sincerely Yours,



Malis Edward  
Logistics Officer  
Malis Edward; Logistics officer  
Plot No. 246, Block 3k 2<sup>nd</sup> Class Residential,  
Tonging Behind Indian Embassy,  
Central Equatoria State,  
Juba South Sudan  
M: +211 (0) 914 992 287· M: +211 (0) 926 595 060  
[malis.edward@malteser-international.org](mailto:malis.edward@malteser-international.org)  
[www.malteser-international.org](http://www.malteser-international.org)  
Malteser International Europe/Malteser Hilfsdienst e. V., County Court Cologne, VR 4726  
Executive Board: Karl Prinz zu Löwenstein, Dr. Elmar Pankau,  
Douglas Graf Saurma-Jeltsch, Verena Hölken



Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

## Instructions to Bidders

### Introduction

Rehabilitation of Water System Infrastructure at three (3) Primary Schools Gumbo Basic Primary School; Rajaf West primary School and Kapuri Primary School in Juba County South Sudan.

<i>The RFQ identification reference is reposted</i> RFQ_JUB_2023_0207	<b>The works include:</b> Rehabilitation of Water System Infrastructure at three (3) Primary Schools Gumbo Basic Primary School; Rajaf West primary School and Kapuri Primary School in Juba County South Sudan
<i>Contact for correspondence, notifications, and requests for clarifications</i>	All correspondence, notifications, and requests for clarification in relation to this reposted RFQ shall be sent to: Malis Edward via <a href="mailto:malis.edward@malteser-international.org">malis.edward@malteser-international.org</a>
<i>Bidder Eligibility</i>	Malteser International will only contract a single legal entity.
<i>Clarifications</i>	Requests for clarification from bidders will not be accepted any later than <b>3 days</b> before the deadline for submission of quotations.
<i>Site Inspection</i>	Before submitting the quotation, the Bidder advised to complete a visit to the project sites to familiarize itself with the condition of the site. MI will not provide support for visits to the project sites. Failure to visit the site shall be deemed a Bidder's risk and shall not be accepted by MI, at any time, as a reason for failure to meet the requirements of the Contract Agreement. In submitting a quotation, it is assumed that the Bidder has visited the sites.
<i>Quotation validity period</i>	Quotation shall remain valid for acceptance by the employer for two months from the deadline for submission of quotations.
<i>Quotation Currency</i>	Prices shall be quoted in United States Dollars (USD).
<i>Duties and Taxes</i>	The Bidder shall price his quotation including all duties, taxes, levies, and other charges in force in the South Sudan.
<i>Language of quotations</i>	All quotations, information, documents, and correspondence exchanged between Malteser International and the bidders in relation to this quotation shall be in English

<i>Quotation Submissions</i>	Quotations shall be submitted via: <b><a href="mailto:mb.procurement-Juba@malteser-international.org">mb.procurement-Juba@malteser-international.org</a></b>
<i>Deadline for Submission of Quotations</i>	All quotations must be submitted by <b><u>7<sup>th</sup> November 2023 at or before: 12:00 pm</u></b>
<i>Quotation Opening</i>	Quotations will be opened by MI Evaluation Committee.

### Technical Proposal

**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**  
Technical information should be prepared in the following manner:

- a. The Bidder shall prepare a method statement inclusive of a preliminary program as part of their quotation. It shall be utilised to assess the Bidders understanding of the project and logical progression of works to facilitate phased renovation in an effective, efficient and safe manner. The method statement shall at a minimum:
  - i. Realistic Work schedule,
  - ii. proposed staff details and CVs of Construction manager and Site Engineer,
  - iii. projected build-up of tools and equipment on site for each phase,The preliminary works schedule shall be as detailed as possible. It shall show the level of detail appropriate to each stage of the Works and all activities each of which shall be given a short title. In his preliminary programme of works, the Contractor shall identify all the constraints he envisages to the timely mobilisation.
- b. All supporting documentation required by this Reposted RFQ including but not limited to:
  - i. Signed Client references from previous projects,
- c. Any other documents as required by this Reposted RFQ or the Employer and this shall include:
  - ✓ **Legal Status of the Company and Information required includes** Principal Place of Business & Addresses (Location, Office Telephone, and Email); Full Details of Company Representative (Name, Title, Telephone & E-mail); Copy of Relevant Certificates (Renewed Registration Certificate, Copy of Valid Trading License - FY 2020/2022, Copy of Income Tax Clearance Certificate-FY 2023 and VAT Registration Certificate.
  - ✓ **Financial Situation of the Company:** Bank statement for the last three months
  - ✓ **Experiences and Works References and information required includes** Provide for project name, value, brief description of scope of works and location of any 2 recent similar projects completed; Provide completion certificate of Works as proof of evidence and provide Referees for recently completed projects mentioned above (Name of contact person, Title and contact details– Telephone & Email)
  - ✓ **Manpower Requirement:** Provide proposed Project Manager and Site Foreman assigned for the engagement (Names, Qualifications, CVs and Years of Relevant Experience) and provide Details of relevant project staff deployed for the engagement (Categories/ Roles and number of staff),
  - ✓ **Plant and Equipment:** Provide lists of relevant plants and equipment owned or leased to be used for the Works. Provided list of key equipment,

#### ***Financial Proposal:***

Financial Proposal should consist of a completed BOQ (including Summary Sheet). Please note that all sums given in quotations must be in the currency as stated in the Contract Agreement.

- a) The Bidder shall fill in rates and prices for all items of the Works described in the Bill of Quantities. Items, for which no rate or price is entered by the Bidder, will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of Quantities,
- b) The Bill of Quantity received with this document shall not be modified,
- c) Where the Bidder observes errors or omissions in the quantities and/or prices stated, these shall be brought to the attention of the Contracting Party not later than three days before the deadline.

The original and all copies of the quotation shall be typed or written in indelible ink and shall be signed by a person or persons duly authorised to sign on behalf of the Bidder. All pages of the quotation shall be initialled by the person or persons signing the quotation.

#### **1.0 Quotation Opening and Evaluation**

The Evaluation Committee will open the quotations. MI will record the quotation opening strictly in accordance with MI procedure.

The Bidders will not be invited to the quotation opening.

Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

**Non-Compliant Quotations**

The MI’s decision on whether a quotation is compliant or not will be final.

**Evaluation and Award**

**Evaluation Method**

Quotations shall be evaluated according to the following procedure:

Firstly, quotations shall be evaluated for technical compliance based on:

- Technical expertise and implementation methodology,
  - Previous experience in similar project and
  - Resources and key personnel.
- a. The set criteria shall be used to determine the most economically advantageous quotation for contract award,
  - b. The Bidder’s initial proposal should contain the quotation’s best terms from a cost or price and technical standpoint,
  - c. If quotations are determined to be equivalent based on the technical criteria, price will then become the deciding criterion for award,
  - d. Bidders are forewarned that an acceptable proposal with the lowest price may not be selected if award to a higher-priced proposal affords MI a greater overall benefit,
  - e. The MI will favourably evaluate a schedule, which shows earlier completion than the MI’s required time frame. The Bidder’s innovative approaches to accomplish early completion are encouraged.

**Clarification of Quotations**

The MI may request clarification or further information in writing from the Bidders at any time during the quotation process. The Bidders’ responses shall not contain any changes regarding the substance or price of the quotation.

**Award of Contract Agreement**

**Notification of award and signing of Agreement**

- a. The notification of award will be informed to the successful Bidders,
- b. The Contract Agreement will comprise the entire agreements between the MI and the successful Bidder. It will be signed by the MI and sent to the successful Bidder. Within 2 days of receipt, the successful Bidder will sign the Contract Agreement and deliver it to the MI.

**Checklists of Documents to be returned.**

The following checklists are included to help remind the Bidders that the quotations submission shall include the following documents for the quotations. Documents shall be compiled in the order specified below:

<b>List of documents to be submitted</b>
a) Legal status information of the company: Principal Place of Business & Addresses, Full Details of Company Representative, and Copy of Relevant Certificates
b) Detailed CVs of Key team members (Project Manager and Site Engineer/Foreman)
c) Bank statement for the last three months
d) Plant, tools, and equipment to be deployed for the engagement
e) Experiences and Works References: Provide project name, value, brief description of scope of works and location of any 4 recent similar projects completed and completion certificate of Works as proof of evidence; provide Referees for recently completed projects mentioned above
f) Realistic Works Schedule
g) Company’s official address,
h) Bank account details (where money would be paid)

**The following are exclusion criteria:**

Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

**1. Not submitted the following company registration documents in South Sudan:**

- 1.1.1. Copy of the company's certificate of incorporation,**
- 1.1.2. Copy of Chamber of Commerce registration,**
- 1.1.3. Copy Tax Identification Certificate,**
- 1.1.4. Copy of Certificate of Operation,**

**2. Not bided according to the specification and**

**3. Mathematical error of total bided price  $>\pm 2\%$ .**

**Appendix to quotation**

Item	Data
Contracting Party	MI
Governing Law	Law of the Country – Republic of South Sudan
Language	English
Provision of Site	On the Commencement Date
Contractor's Representative	To be notified in writing by the Contractor
Time for Completion	One months
Programme: Time for submission	Within 5 days of Commencement Date
Delay Damages	0.10% of Contract Price per day up to a maximum of 10%
Defects liability period	3 months calculated from the date stated in the notice under Sub-Clause 6.5
Percentage of retention	10% of the payment for six months
Currency	US Dollars

**Conditions**

**1. General Provisions**

1.1 Definitions

- 1.1.1 "Variation" means a change to the Specifications and/or Drawings (if any), which is instructed by the Malteser International,
- 1.1.2 "Date of Substantial Completion" means the date when the Works have reached substantial Completion as stated in the Taking-Over Certificate,
- 1.1.3 The "Defects Notification Period" means the period for notifying defects in the Works,
- 1.1.4 The "Final Completion Certificate" means the certificate issued under Sub-Clause **9.4**,
- 1.1.5 "Taking-Over Certificate" means a certificate issued under Clause **6.5** certifying that the Works have reached Substantial Completion and stating the date of Substantial Completion,
- 1.1.6 'Contract' means the Agreement and other documents listed in the Appendix,
- 1.1.7 'day' means calendar day.
- 1.1.8 'Force Majeure' means an exceptional event or circumstance which is beyond a Part's control; which such party could not have provided against before entering contract; which, having arisen such Party could not reasonably have avoided or overcome, and which is not substantially attributable to other party.

1.2 Communication

- 1.2.1 The Contractor shall neither seek nor accept instructions from any authority external to Malteser International in connection with the performance of its obligations under the Contract.

1.3 Assignment

- 1.3.1 The Contractor shall not assign, transfer, pledge or make other disposition of this Contract or any part thereof, or any of the Contractor's rights, claims or obligations under this Contract except with the prior written consent of the Malteser International,

1.4 Malteser International's Use of Contractor's Documents,

- 1.4.1 As between the Parties, the Contractor shall retain the copyright and other intellectual property rights in the Contractor's Documents and other design documents made by (or on behalf of) the Contractor. The

**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

Contractor gives and shall be deemed (by signing the Contract) to give to the Malteser International a perpetual, non-terminable, transferable non-exclusive, royalty-free, worldwide license to copy, use and communicate the Contractor's Documents, including making and using modifications of them,

**1.5 Confidential nature of Documents and Information**

1.5.1 The Contractor shall treat the details of the contract as private and confidential, except to the extent necessary to carry out obligations under it or to comply with applicable Laws.

1.5.2 All information provided to either party by either party shall be held in confidence by all Parties,

**1.6 Law**

1.6.1 The law of the contract is stated in the Appendix,

**2. The Malteser International**

**2.1 Provision of Site,**

2.1.1 Malteser International shall provide the site in the presence of the authority.

**2.2 Malteser International instructions,**

2.2.1 The contractor shall comply with all instructions given by the Malteser International in respect of the Works including the suspension of all or part of Works,

**2.3 Approvals**

2.3.1 No approval or consent or absence of comment by Malteser International or the Malteser International's representative shall affect the Contractors obligation.

**3. Engineer / Malteser International's Representative**

3.1 The Malteser International may appoint an Individual to carry out certain duties.

**4. The Contractor**

**4.1 General obligation**

4.1.1 The Contractor shall carry out Works Properly and in accordance with the contract. The Contractor shall provide all the supervision, labour, Materials, Plant and Contractor's equipment which may be required.

**4.2 Contractors representative**

4.2.1 Contractor shall submit to the Malteser International the name and particulars of the person authorized to receive instructions on behalf of the Contractor,

**4.3 Subcontracting**

4.3.1 The Contractor shall not subcontract the whole of the works. The contractor shall not subcontract any part of the Works without consent of the Malteser International,

**4.4 Performance Security**

4.4.1 Contractor shall deliver to the Malteser International within 60 days of commencement date a performance security in a form and from third party approved by the employer,

**4.5 Safety Procedures**

4.5.1 The Contractor shall comply with the requirements of the specification and all applicable local and national laws governing the health and safety requirements for the protection of employees and any others entering the Site,

**4.6 Site Data**

4.6.1 The Contractor shall be deemed to have obtained all necessary information as to risks, contingencies and other circumstances which may influence or affect the quotation or Works. To the same extent, the Contractor shall be deemed to have inspected and examined the Site, its surroundings, the above data and other available information, and to have been satisfied before submitting the quotation,

**4.7 Sufficiency of the Contract Amount**

4.7.1 The Contractor shall be deemed to:

- a) have satisfied himself as to the correctness and sufficiency of the Contract Price, and
- b) have based the Contract Price on the data, interpretations, necessary information, inspections, examinations and satisfaction as to all relevant matters referred to in Sub-Clause 4.6.,



**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

4.7.2 Unless otherwise stated in the Contract, the Contract Price covers all the Contractor's obligations under the Contract and all things necessary for the proper execution and completion of the Work and the remedying of any defects,

#### 4.8 Contractor's Equipment

4.8.1 The Contractor shall be responsible for all Contractor's Equipment. When brought on to the Site, Contractor's Equipment shall be deemed to be exclusively intended for the execution of the Works. The Contractor shall not remove from the Site any major items of Contractor's Equipment without the written consent of Malteser International. Consent shall not be required for vehicles transporting Goods or Contractor's Personnel

#### 4.9 Supply of Electricity and Water

4.9.1 The Contractor must provide on the Site, for the duration of the Works, an adequate supply of drinking and other water for the use of its staff and labour. The Contractor shall also provide power and other services required for him to undertake the Works.

#### 4.10 Progress Reports

4.10.1 Progress reports shall be prepared by the Contractor and submitted to the Malteser International's Representative containing the project progress information required by the Contract. The Contractor shall issue the report in the number of copies and at the intervals stated in the Scope of Works.

#### 4.11 Contractor's Personnel

4.11.1 The Contractor's Key Personnel are named in the quotation. The Contractor must not replace the Key Personnel without prior written consent of the Malteser International and must submit to the Malteser International for approval the names and particulars of the persons the Contractor proposes to replace.

4.11.2 The Contractor's Personnel must be appropriately qualified, skilled, and experienced in their respective trades or occupations. The Malteser International may require the Contractor to remove (or cause to be removed) any person employed on the Site or in the execution of the Works, including the Contractor's Representative who in the opinion of the Malteser International,

- a) persists in any misconduct or lack of care,
- b) carries out duties incompetently or negligently,
- c) fails to conform with any provisions of the Contract or
- d) persists in any conduct which is prejudicial to safety, health, or protection of the environment.

4.11.3 Where this Sub-Clause 4.11.2 applies, the Contractor must then appoint a suitable replacement person for each person so removed.

4.11.4 The Malteser International will not be liable for or in respect of any damages or compensation payable at law in respect or in consequence of any accident or injury to any of the Contractor's Personnel, unless resulting from any act or Default of the Malteser International.

### 5. Malteser International Liability

5.1 In this Contract, Malteser International's Liabilities mean:

- a) Force Majeure,
- b) a suspension under Sub-Clause 2.2 unless it is attributed to the Contractor's failure, act, omission or breach.

### 6. Time for completion and take over

#### 6.1 Execution of the Works

6.1.1 The contractor shall commence the works on the commencement date and shall proceed expeditiously and without delay and shall complete the works within the Time for Completion.

#### 6.2 Extension of time

6.2.1 Subject to clause **8.3** the contractor shall be entitled to an extension of Time for completion if he is or will be delayed by employers Liabilities. On receipt of the application, Malteser International shall consider all the supporting details provided by the contractor and shall extend the time for completion as appropriate.

#### 6.3 Late Completion

**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

6.3.1 If the Contractor fails to complete the Works within the Time for completion, the contractor's liability to the Malteser International for such failure shall be to pay amount sated in the Appendix for each day for which he fails to complete the works.

6.4 Take-Over

6.4.1 The contractor may notify the employer when he considers that work is complete.

6.5 Take-Over Notice

6.5.1 Malteser International shall notify the contractor when he considers that the contractor has completed the works stating the date accordingly. Malteser International shall take over the works upon the issue of this notice. The contractor shall promptly complete all the outstanding works and subject to clause 7 clear the site.

## **7. Remedying Defects**

7.1 Malteser International may at any time prior to the expiry of the period stated in the appendix, notify the contractor of any defects or outstanding work. The contractor shall remedy at no cost to the employer any defects due to the contractors design, materials, plant or workmanship not being in accordance with the contract.

## **8. Variations and Claims**

8.1 Right to Vary

8.1.1 The Malteser International may instruct Variations.

8.2 Valuation of Variations

8.2.1 Variations shall be valued as follows.

- a) At lump sum price agreed between the Parties,
- b) Where appropriate at rates in the contract or
- c) In the absence of rates, the rates in the Contract shall be used as the basis for valuation or failing which,
- d) At appropriate new rates, as may be agreed or which the employer considers appropriate.

8.3 Early Warning

8.3.1 A Party shall notify the other as soon as he is aware of any circumstance which may delay or disrupt Works, or which may give rise to a claim for additional payment. The contractor shall take all reasonable steps to minimize these effects. The contractor's entitlement to extension of time for completion or additional payment shall be limited to the time and payment which would have been due if he had given prompt notice and had taken all reasonable steps.

8.4 Variation and Claim Procedure.

8.4.1 The contractor shall submit to Malteser International an itemized makeup of the value of the variations and claims within 28 days of the Instruction or of the event giving rise to the claim. Malteser International shall check and if appropriate agree the value. In the absence of agreement, Malteser International shall determine the value.

8.5 Adjustment for Changes in Cost

8.5.1 Unless otherwise expressly stated, the Contract Price, and the rates and prices inserted in the Bill of Quantities, will not be adjusted for rises or falls in the cost of labour, goods and other inputs to the Works and the Contract Price and the rates and prices inserted in the Bill of Quantities, will be deemed to include amounts to cover contingency of rises and falls in the cost of labour, goods and other inputs to the Works.

## **9. Contract Price and Payment**

9.1 Valuation of Works

9.1.1 The Malteser International shall pay the Contract Price in accordance with this Clause 9 and the Scope of Works annexed to the Contract. The Contractor is deemed to have satisfied itself as to the correctness and sufficiency of the Contract Price and all fixed unit rates and prices in the Contract.

9.2 Interim Payment

9.2.1 Within 28 days of delivery of each statement submitted, the Malteser International will pay to the Contractor the amount shown in the Contractor's statement less retention at the rate specified in the Appendix to quotation and less any amount to be deducted for Advance Payment (if any) and repayments (if any), and



**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

less any other amount for which the employer has specified its reasons for disagreement or that has become due under the Contract. Malteser International is not bound by any sum considered to be due by the Contractor.

9.2.2 Malteser International may withhold interim payments until it receives the performance guarantee under Sub-Clause 4.4 (if any).

**9.3 Payment of Retention**

9.3.1 The retention will be paid by Malteser International to the Contractor within 14 days after four months of completion of the work.

**9.5 Payment**

9.5.1 Within 14 days after receiving the Final Completion Certificate, the Contractor must submit a final account to the Malteser International together with any documentation reasonably required to enable the Malteser International to ascertain the final contract value.

**9.6 Delayed Payment**

9.5.1 The Contractor is not entitled to any interest in respect of any amount in any statement submitted to Malteser International which remains due and unpaid.

**10. Default and termination**

**10.1 Default by the Contractor**

10.1.1 If the Contractor abandons the Works, refuses, or fails to comply with a valid instruction of the Malteser International or fails to proceed expeditiously and without delay, or is in breach of the Contract, the Malteser International may give notice referring to this Sub-Clause and stating the default.

10.1.2 If the Contractor has not taken all practicable steps to remedy the defaults with 14 days after the Contractor's receipt of the Malteser International's notice, the Malteser International may by a second notice of 14 days, terminate the Contract.

10.1.3 The Malteser International reserves the right to terminate the Contract immediately without written notice if the Contractor is declared insolvent or is in breach of the contract.

10.1.4 If Malteser International serves a termination notice under this Sub-Clause 10.1, the Contractor must stop work and demobilize (except to the extent specified in the notice from Malteser International).

**10.2 Payment upon Termination**

10.2.1 After termination, the Contractor shall be entitled to payment of the unpaid balance of the value of the Works executed and of the Materials and Plant reasonably delivered to the Site, adjusted by the following:

- a) any sums to which the Contractor is entitled.
- b) any sums to which the Malteser International is entitled,
- c) if the Malteser International has terminated under Sub-Clause 10.1, the Malteser International shall be entitled to a sum equivalent to 10% of the value of those parts of the Works not executed at the date of the termination,

**10.3 Malteser International's Entitlement to Terminate for Convenience**

10.3.1 The Malteser International may in its absolute discretion terminate the Contract, at any time for the Malteser International's convenience, by giving notice of such termination to the Contractor. The termination will take effect 28 days after the later of the dates on which the Contractor receives this notice, or Malteser International returns the Bank Guarantee for performance.

**11. Risks and Responsibility**

**11.1 Contractor's Care of the Works**

11.1.1 The contractor shall take full responsibility for the care of the works from the commencement date until the employer takes over the completed works.

**11.2 Force Major**

11.2.1 If a party is or will be prevented from performing any of its obligations by force Majeure, the party affected shall notify the other party immediately. If necessary, the contractor shall suspend the execution of works and to the extent agreed with the employer demobilize the contractor's equipment.

**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

If the event continues for a period of 84 days either party may give notice of termination which shall take effect 28 days after giving the notice.

## 12. Insurance

12.1 The contractor shall, prior to commencing the works effect and thereafter maintain insurances for the Works, Materials, Plants and contractor's equipment and Manpower including third parties.

## 13. Resolution of Disputes

13.1 Resolutions of Disputes

13.1.1 Disputes shall be settled amicably.

### Bill Of Quantities

#### Rehabilitation of Water System Infrastructure at three (3) Primary Schools Gumbo Basic Primary School; Rajaf West primary School and Kapuri Primary School

S/No	Description	Unit	Qty	Rate USD	Amount USD
<b>Chain link fence Gumbo Basic - (8MX6M)</b>					
1.01	Preconstruction works, mobilization and demonization of existing chain-link fence and clearing arising from the site	L-s	1		-
	Sub-total 1				-
2.00	<b>Erection of chain link Fence size (8MX6M)</b>				
2.01	Supply and erect a Chain Link 7ft height (G 12.5) supported with tension wire in four phases and binded for additional support	M	28.00		-
2.02	Supply and install a fabricated well painted Angle bar (50x50x3mm painted black at 2000mmC/C casted at 400mm in the ground and at the top fabricated at V-shape to receive the razor wire (Note all corners and after every 8 meters is well supported)	No	16.00		-
2.03	Cast a concrete M20 for the installed poles, bottom of the chain links all around the fence in nice finishes (0.4x0.25) at the mix ratio of 1:2:4	Cu.m	2.50		-
2.04	High tensile steel bars (12mm and 8mm) including cutting bending tying, hooking, and fixing for circular columns, beams	kg	8.00		-
2.05	Supply and erect with stainless steel strings/Plain wire a razor wire on the top of the chain link fence including the metal works on the concrete fence	M	85.00		-
2.06	Supply and install a fabricated gate including painting using 50*50*3mm LH metal as frames and SHS 40*40*3mm shutters including proper locking system other requirments like 2 padlocks	L.S	1.00		-
2.07	<b>supply coarse</b> aggregate 3/4" and level it at the water sources at 0.2 thickness for all the three schools water sources	cu.m	18		-
2.08	<b>Security light with its solar</b> light medium size complete and its acessories installed at the water source	pcs	1		-

Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

2.09	<b>Sensor</b> supply and installed sensor at the water tank in Gumbo basic primary school	No	1		-
2.10	<b>Paint</b> Re-painting of the metallic tower	L-s	1		-
	Sub-total 1				-
3	<b>RAJAF WEST PRIMARY SCHOOL</b>				
3.01	<b>Security solar</b> light medium size complete with poles and its accessories at the water point to community	No	1		-
3.02	<b>Painting</b> Re-painting of the metallic tower	L.S	1		-
	Sub-total 2				-
4	<b>KAPURI PRIMARY SCHOOL</b>				
4.01	<b>Security solar</b> light medium size complete with a pole and its accessories at the water point to community	No	1		-
	Sub-total 4				-
	<b>Grand Total</b>			<b>USD</b>	-

## Technical Specifications

### 1.1 MATERIALS GENERALLY

All materials used in the works shall be new and of the qualities and kinds specified herein and equal to the approved samples. Materials and methodology for the execution of the works shall be submitted to for to the Employers Representative for relevant approval before commencement of the works. Non approved material incorporated in the works, will make the executed works null and void to all fields and shall be removed and replaced with the approved ones at the contractor's expense and care, in this case the contractor will not be eligible for extension of time.

#### 1.1.1 Samples

The Contractor shall furnish for approval with reasonable promptness all samples of materials and workmanship required by the employer. The employer shall check and approve such samples for conformance with the design concept of the works and for compliance with the information given in the Contractor Documents.

### 1.2 EXCAVATIONS AND EARTHWORK

#### 1.2.1 Inspection of site

The Contractor is deemed to have visited the site and to have ascertained the nature of the soil and sub-soils to be excavated. No claim will be made on account of these being of a different nature from that which he has allowed in his prices.

**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

### **1.2.2 Existing trees and shrubs**

No shrubs, trees or plants shall be removed except as directed by the employer's representative. The contractor shall be held responsible for any damage caused by the building operations to those shrubs, trees etc. not so directed to be removed.

### **1.2.3 Site Clearance**

All vegetation matter must be removed or burned on site at the commencement of the contract over areas as directed by the employer's representative.

### **1.2.4 Excavation**

If the Contractor excavates to any widths or depths greater than those shown on the Drawings or as instructed by the employer's representative, the contractor shall at his own expense fill in such widths or depths of excavation beyond that instructed or shown with concrete to the satisfaction of the employer's representative.

### **1.2.5 Materials found in the excavations.**

No sand, aggregate or other materials found in the excavations is to be used in the works without the written permission of the employer's representative.

### **1.2.6 Rates for Excavations**

The rates for excavation including excavation in hard ground, must include for trimming, levelling, preparing bottoms and all faces to receive concrete, any extra excavation required for planking and strutting and disposal of excavated material.

Prices shall include for excavating in any material encountered unless specifically otherwise described.

## **1.3 CONCRETE WORK**

### **1.3.1 Generally**

All workmanship, materials, tests, and performance in connection with the reinforced concrete work are to be in conformity with the British Standard Code of Practice (BS 8110; 1985, incorporating the latest amendments thereto), for "the Structural use of Reinforced Concrete in Buildings" and in accordance with local by-laws.

### **1.3.2 Cement**

Cement unless otherwise specified, shall be Portland Cement of a brand approved by the Employers Representative and shall comply with the requirements of BS 12 with the exceptions that it may contain reactive volcanic ash (of not more than 10% of the total weight) and the quantity of insoluble residue permitted in BS 12 may be exceeded.

### **1.3.3 Aggregates**

Aggregates shall conform to the requirements of BS 582 and the sources and types of all aggregates are to be approved in all respects by the Engineer before work commences.

Coarse aggregate shall be good, hard, clean, and free from dust decomposed stone, clay earthy matter, foreign substances or friable thin elongated or lamed pieces. It shall be graded with the limits of

Aggregate shall be delivered to the site in their prescribed sizes or grading.

### **1.3.4 Water**

The water used for mixing concrete shall be from an approved source, clean, fresh and free from harmful matter, and comply with the requirements of BS 3148.

Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

### **Concrete Mix proportion and strength.**

- The mixed ratio for reinforced concrete shall be in the proportion 1:2:4 (cement: sand: aggregate).
- Water – cement ratio for concrete shall be 0.4% to 0.45%.
- Reinforced concrete shall have minimum 28-day strength of 20 N/mm<sup>2</sup>.
- The required slump of the concrete shall be 100mm ±20mm.
- The mixture ratio for mass concrete reinforced concrete shall be in the proportion 1:3:6 (cement: sand: aggregate).
- 20mm aggregate to be used for both Mix proportions.

### **1.3.5 Compaction**

At all times during which concrete is being placed the Contractor shall provide adequately trained and experienced labor to ensure that the concrete is compacted in forms to the satisfaction of the Engineer.

### **1.3.6 Curing and Protection**

Care must be taken that no concrete is allowed to become prematurely dry, and the fresh concrete must be carefully protected within two hours of placing from rain, sun and wind by means of hessian sacking, polythene sheeting, or other approved means. This protective layer and the concrete itself must be kept continuously wet for days after the concrete has been placed.

### **1.3.7 Faulty Concrete**

Any concrete which fails to comply with these Preambles, or which shows signs of setting before it is placed shall be taken out and removed from the site. Where concrete is found to be defective after it has set, the concrete shall be cut out and replaced in accordance with the employer's representative's instructions. On no account shall any faulty honeycombed, or otherwise defective concrete be repaired or patched until the Employer's Representative has inspected and issued instructions for the repair. The whole of the cost whatsoever, which may be occasioned by the need to remove faulty concrete shall be borne by the Contractor.

### **1.3.8 Reinforcement**

All reinforcement shall be free from loose mill scale or rust, grease paint or other substances likely to reduce the bond between the steel and concrete.

### **1.3.9 Fabric Reinforcement**

To be electrically cross-welded steel wire mesh reinforcement to BS 4483(1969) and of the size and weight specified.

## **1.4 MASONRY**

### **1.4.1 Masonry Units**

Masonry units shall be as indicated in the drawings and as follow:

- Burnt clay bricks
- Concrete solid blocks

### **1.4.2 Mortar and Bonding**

Bonding mortar of 1:4 (cement: sand) ratio shall be used immediately after mixing, and mixed mortar left for more than one hour shall be rejected. Vertical and horizontal joints shall be filled completely. The spacing between the blocks in the wall is to be 10mm and raked to receive plaster.

Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

## **1.5 CARPENTRY AND JOINERY**

### **1.5.1 Generally**

All woodwork shall be carried out in accordance with the drawings and the principles of first-class joinery construction. Unless specifically stated otherwise sizes shown on drawings are finished sizes and the Contractor must allow for wood faces.

### **1.5.2 Defective Work**

All work judged to be defective must be removed and replaced as directed by the employer's representative.

## **1.6 METALWORK**

### **1.6.1 Generally**

All material shall be the best of their respective kinds free from defects and all work is to be carried out in the most workmanlike manner. The materials in all stages of transportation, handling and stacking shall be kept clean and prevented from injury by breaking, bending or distortion and weather action.

### **1.6.2 Metal Works (Doors)**

All work shall be carried out strictly as indicated in the drawings, BOQ and approved by Employers Representative. Metal work to be painted shall be scaled clean and thoroughly wire brushed. All steel works shall be primed with a red lead primer (red oxide) before applying the final coat of oil paint using approved brand and color.

a) Manufacturing of doors grills shall be constructed with 2 mm steel plate thickness. Before manufacturing the doors, the Contractor shall control and verify the exact measurements on site.

## **1.7 FINISHINGS**

### **1.7.1 Other specifications**

All other specifications of this contract where applicable are deemed to apply equally to the finishing's specifications.

### **1.7.2 Finished thicknesses.**

The thickness of floors shall have a constant structural thickness and have level top surfaces. The finished floor surface will equally have a constant level and any adjustment needed to achieve this effect with the varying floor finish materials is to be made in the screens beneath the same.

Slabs bearing on the ground may be cast to varying levels, and be of constant thickness with varying formation levels, or have varying thicknesses at the option of the Contractor. This stipulation in no way relieves the Contractor of the requirements of the specification for structural work.

### **1.7.3 Plaster**

<b>Item of Work</b>	<b>Mix</b>
Internal plaster	1 part cement 3 parts sand
External Render	1 part cement 3 parts sand

### **Curing of plaster**

Each coat of plaster is to be maintained in a moist condition for at least three days after it has developed enough strength not to be damaged by water.

### **Cement and sand screeds**

Screeds shall be mixed and formed as described.



Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany

## ***PAINTING***

### **Materials**

#### **1.7.4 Manufacturers**

Except where stated all materials shall be obtained from an approved manufacturer. The Contractor shall state the name and address of the manufacturer whose materials be proposed to use. Once approval has been given the Contractor shall not obtain materials from other sources without the prior written agreement of the Employer.

#### **1.7.5 General**

Each succeeding coat of priming, undercoating, and finishing (pigment) of clear coating shall be sufficiently differently different in color as to be readily distinguishable.

All primers and paints in one system upon a particular surface shall be obtained from the same manufacturer.

The mixing of paints etc., of different brands before or during application will not be permitted.

#### **1.7.6 Emulsion paints**

Emulsion paints shall be matt or satin finish vinyl emulsion paint.

The first (mist) coat shall be thinned in accordance with the manufacturer's instructions.

#### **1.7.7 Gloss paint**

Gloss paint shall be hard gloss finish oil paint.

#### **1.7.8 Primers and undercoats**

Unless otherwise specified, primers and undercoats shall be of the type recommended by the manufacturer of the finishing coats specified for a particular surface. Primer for external bare metal work surfaces shall comply with BS 2523.

#### **1.7.9 White spirit**

The white shall comply with BS 245

#### **1.7.10 Inspection**

No priming coats shall be applied until the surfaces have been inspected and preparatory work has been approved by the employer's representative. No undercoats or finishing coats shall be applied until the previous coat has been similarly inspected and approved.

#### **1.7.11 Paint application**

Each coat of paint shall be applied to produce a film of uniform thickness. All paint shall be used in accordance with the manufacturer's instructions. Special attention shall be given to ensure that all surfaces including edges, corners, crevices, welds, and rivets receive a film thickness equivalent to that of adjacent painted surfaces.

#### **1.7.12 Colors**

The colors will be selected by the employer's representative from the paint manufacturer's standard color range.

#### **1.7.13 Protection**

Proper care must be taken to protect surfaces while still wet by using screens and 'wet paint' signs where necessary.

#### **1.7.14 Damage**

Care must be taken when preparing surfaces or painting etc. not to stain or damage other work. Dust sheets and covers to the satisfaction of the Architect shall be used to protect adjacent work. Any such stains or damage shall be removed and made good at the Contractor's expense.

**Malteser Hilfsdienst e. V., Malteser International, Erna-Schaeffler-Str. 2, 51103 Cologne, Germany**

**Cleaning and handing over.**

The site shall be cleared of any debris arising from the works and disposed of in an area approved by the local authority. All completed structure shall be washed clean before handing over.

Yours faithfully,



Malis Edward  
Logistics Officer  
Malis Edward; Logistics officer  
Plot No. 246, Block 3k 2<sup>nd</sup> Class Residential,  
Tonging Behind Indian Embassy,  
Central Equatoria State,  
Juba South Sudan  
[malis.edward@malteser-international.org](mailto:malis.edward@malteser-international.org)  
[www.malteser-international.org](http://www.malteser-international.org)  
Malteser International Europe/Malteser Hilfsdienst e. V., County Court Cologne, VR 4726  
Executive Board: Karl Prinz zu Löwenstein, Dr. Elmar Pankau,  
Douglas Graf Saurma-Jeltsch, Verena Hölken

Legal advice: This communication is for use by the intended recipient and contains information that may be privileged, confidential or copyrighted under applicable law. If you are not the intended recipient, you are hereby formally notified that any use, copying or distribution of this e-mail, in whole or in part, is strictly prohibited. Please notify the sender by return e-mail and delete this e-mail from your systems.

**Please consider the environment before printing this email**