



**BILL OF QUANTITY FOR RENOVATION OF FRASKA PRIMARY SCHOOL BUDI
ONE BLOCK OF 3 CLASSROOMS AND OFFICE ROOM**

NO	ITEM DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Preliminaries				
1	Allow for mobilisation and demobilisation including all contractors plant, machinery, equipment, work force to the site and making all necessary preparation for preliminary work.	LS	1		0
1.1	Carefully remove all the damaged ironsheets.	PCS	15		0
1.2	Carefully remove all the damaged ceiling board.	SM	146		0
1.3	Hack and remove all the damaged parts of the floor screed, verandah area and apron and make ready to receive new screed.	SM	70		0
1.4	Carefully Remove all the damaged door frames to make ready for welding using new hinges..	PCS	5		0
1.5	Scrab all the cracked parts of the wall and weak areas of the plastered walls to receive new plaster.	SM	35		0
	Preliminaries totals carried to summery.				0
2	Windows and doors,				
2.1	Using plain metal plate 2mm and hollow section 40X40X2mm cut, fabricate and weld on the window from outside. Size 1.45X1.05M	PCS	14		0
2.2	Supply strong metal hinges and weld all the broken doors size 0.87X2.06M. THIS IS FOR ALL THE CLASSROOM AND OFFICE ROOM.	PCS	4		0
	Totals for doors and windows carried to summry				0
0					
3	ROOFING				
3.1	Supply and fix ironsheets G28 prepainted and maintaining the same colour on the leaking parts.	SM	50		0
3.2	Supply and fix fasciaboar on the damaged parts.	LM	70		0
	Roofing total carried to summery				0



	CEILING				
4	Supply and fix timber 50x75mm for blandering on the affected parts, cost includes charges for applying timber preservatives on the timbers for the blandering.	LM	350		0
	Supply and fix ceiling board 1.2X2.4M.	SM	146		0
	Ceiling total carried to summery				0
	Floor and walls				
	On the hacked floor and apron screed 25mm thick morta cement and sand 1:3 finished smooth with steel float.	SM	45		0
	On the scrabbed internal wall replaster cement morta 1:3, finished smooth with wooden float. Rates include refilling the cracks on the walls.	SM	25		0
	On the external wall surface apply rough cast and thoroughly cure the walls for the cement to get stronger.	SM	20		0
	Floor and wall total carried to summery.				0
	Painting				
	Prepare and apply one coat of undercoat and two coats of silk paint on the internal wall surface.	SM	350		0
	Prepare and apply one coat of undercoat and two coats of ceiling paint on the ceiling board.	SM	146		0
	Prepare and apply one coat of undercoat and two coats of weatherguard paint on the external wall surface including the fascia board.	SM	128		0
	Prepare and apply two coats of oil paint on the windows and doors.	SM	60		0
	Total for paint carried to summery				0
	TWO EXTERNAL CONTAINERS 20F				
	On the metal containers cut four windows and one door on each of the container.	LS	1		0
	Supply and fix metal fabricated windows with full metal plate from outside and lockers from inside. Size 1.2X1.5m	PCS	8		0
	Supply and fix metal fabricated doors with strong hines and lockers on the two containers. Size 2mx 0.9M	PCS	2		0
	prepare and apply two coats of paint on the doors and windows.	SM	37		0



	Total carried forward from the two containers.				0
	SUMMARY				
	TOTALS FOR CLASSROOMS AND OFFICE RENOVATIONS				0
	TOTALS FOR RENOVATING TWO CONTAINERS FOR CLASSROOMS				0
	5% CONTIGENCY FOR ANY UNFORE SEEN WORK.				0
	GRAND TOTALS				0

