

BILL OF QUANTITY FOR THE CONSTRUCTION OF PIT LATRINES					
ITEM	DESCRIPTION	UNIT	QUANTITY	Unit cost	Total cost (USD)
1	PRELIMINARY SITE CLEARANCE				
0.1	site clearance of all grass,shrubs,debris,undergrowth including small trees.		1		
0.2	Excavation of pit with dimensions of 3.3lengthx2.7werthsx3.7deeps.		32.0		
	Total for preliminaries		SUB-TOTAL	0	0.00
A	CONSTRUCTION OF FOUNDATION AND SUBSTRUCTURE				
A.1	burn bricks	pcs	9000		
A.2	cements	pcs	30.0		
A.3	iron bars y12	pcs	17.0		
A.4	iron bars y6	pcs	12.0		
A.5	Wire mash	pcs	8.0		
B.1	biding wire	ROLLS	1.0		
B.2	poles bended for the slabs 6x2	pcs	12.0		
B.3	river sand	m3	32.0		
B.4	aggregate	m3	5.0		
	Subtotal 2		SUB-TOTAL	0.0	0.00
C	SUPERSTRUCTURE				
C.1	iron sheet gauge 28 blue in colour	pcs	16.0		
C.2	timbers 1x8	pcs	5.0		
C.3	timbers 4x2	pcs	22.0		
cd	timber 3x2	pcs	18.0		
C.5	wild cliffs	pcs	20.0		
C.6	roofing nails	ROLLS	5.0		
C.7	assorted nails	Piece	10.0		
C.8	t volt	Piece	2.0		
C.9	padlocks	Piece	2.0		
D.1	PVC PIPES	m	2.0		
D.2	head cover	m	2.0		
D.3	transportation cost		0.3		
D.4	water cost		0.2		
D.5	labour cost		0.3		
	SUBTOTAL 4		SUB-TOTAL		0.00
	GRAND TOTAL				
2	SITE CLEARANCE AND EXCAVATION				
3	CONSTRUCTION OF FOUNDATION AND SUBSTRUCTURE				
4	SUPERSTRUCTURE				
	GRAND TOTAL				-