

SAMARITAN'S PURSE SOUTH SUDAN
BILLS OF QUANTITIES
RENOVATION WORKS FOR CONVERSION OF ACCOMMODATION BLOCK TO OFFICE BLOCK

No	Description	Unit	Qty	Rate (USD)	Total (USD)
A	PRELIMINARIES				
A1	Mobilization of tools, equipment, personnel to site	Item	1		-
A2	Sub-Total				-
B	DEMOLITION WORKS				
B1	Toilets in Rooms B1, B2, B3, B6 and B7				
B2	Allow for careful removal of existing plumbing fixtures and dispose or store as directed by client	No	5		-
B3	Careful removal of existing toilet doors and frames	No	5		-
B4	Demolishing of the existing toilet wall to create more space for the office	m²	69		-
B5	Load and dispose all demolished materials away from site or store as directed by client.	Ls	1		-
B6	Sub-total				-
C	TOILET RENOVATIONS				
C1	Tile Works in the Toilets				
C2	Removal and disposal of the existing wall tiles and floor tiles	m²	50.49		-
C3	15mm thick cement/lime/sand (1:4) plaster finished smooth with lime putty or approved equivalent on wall areas where tiles were removed	m²	57.75		-
C4	Place 40mm thick cement-sand (1:3 mix) screed on floor and install tiles provided by SP	m²	17.28		-
C5	Ceiling Works in Toilets				
C6	Note: All ceiling materials shall be provided by SP. Contractor shall provide labour only.				
C7	Provide labour to install 9mm plywood ceiling board	m²	21.6		-
C8	Relocation of Toilet Doors for Rooms B4 and B5				
C9	Demolishing of wall for 2 new door locations	m²	3.96		-
C10	Carefully remove the existing toilet doors and frames, and install them at new locations as shown in the drawings.	No	2		-
C11	Construct 200mm thick block wall in cement sand mortar (1:3) to close the existing door openings after removal of the doors, the rate shall include masonry and plastering	m²	3.96		-
C12	15mm thick cement/lime/sand (1:4) plaster finished smooth with lime putty or approved equivalent on the new walls.	m²	7.92		-
C13	Sub-Total				-
D	REPAINTING OF WALLS AND CEILING				
D1	Internal walls				
D2	Sand and skim the existing internal walls, apply one coat of premier, and two coats of vinyl silk (soft white)	m²	325.92		-
D3	Ceiling				
D4	Sand and skim the existing ceiling, apply one coat of premier, and two coats of matt (white.)	m²	111.22		-
D5	Sub-Total				-
	TOTAL				-