



BILL OF QUANTITIES FOR REHABILITATION OF LATRINES IN HEALTH FACILITIES AND SCHOOLS

Project: South Sudan integrated emergency project (SIEP II)

Project Location: Lainya

Item Number	Item Description	Unit	Quantity	Rate-USD	Amount - USD
Bill (1) No 1 – Kenyi PHCU					
1	Provide and allow for replacement of door frame for 4 doors in 2" x 4" well -seasoned and finished timber work , inclusive of nails and wall cramps 24 No.	No.	24		
2	Provide and allow for carpentry work for replacement of 2" x 3" door shutters for 4 doors, allow for provision of nails and 4" T-hinges 12 No, 4" barrel bolts 4 No.	No	4		
3	Allow for fixing back existing iron sheets on the shutters complete with Rasp and staple with pad locks 4 No. <ul style="list-style-type: none"> - Ditto but 2"x3" purlins - Ditto but 2"x4" rafter - Ditto but iron sheets 24 gauge - Ditto but roofing and pin nails 	Meter Meter Sheet Kgs	16 12 08 03		
4					

	Provide and allow for minor repair work on damaged roof of the latrine block : <ul style="list-style-type: none"> - Ditto but iron sheets - Ditton but timber 2"x4" - Ditto but 2"x3" - Ditto but roofing and assorted ordinary nails - Ditto but pad locks medium size 	Sheets	08		
		Meter	24		
		Meter	16		
		Kgs	10		
		Pieces	04		
5	<ul style="list-style-type: none"> - Provide and allow for painting of 4 door shutters using light blue oil paint - Provide and allow for painting both internal and external wall surfaces of the latrine block 	Sqm	12		
		Sqm	120		
Sub total Bill No 1 – Kenyi PHCU c/t summery					
Bill No 2 – Lokurubang primary school					
1	Provide and allow for replacement of damaged door frames for 4 doors , height 1.80mx width 0.85m : <ul style="list-style-type: none"> - Ditto ditto but 2"x4" - Ditto ditto but wall cramps - Ditto but ordinary pin nail 	Meter	24		
		Pieces	16		
		Kgs	06		
2	Provide and allow for carpentry work for replacement of door shutters for 4 latrine doors complete with provision of locks from inside and outside. <ul style="list-style-type: none"> - Ditto but 2"x3" timber - Ditto but 4" T-hinges - Ditto but 4" barrel bolts - Ditto but pad locks medium size - Ditto but nails assorted 	Meter	40		
		pieces	24		
		Set	04		
		Pieces	04		
		Kg	06		

3	Provide and allow for minor repair on walls and floors , at least 40mm thick plasterer 1:3 cement to sand mortar	Sqm	120		
4	Provide and allow for , at least one coat oil paint on 4 doors	Sqm	12		
5	Provide and allow for at least 2 coats wall paint on internal and external wall surface	Sqm	180		
Sub total bill (2) Lokurubang primary school Latrine c/t summery					
Bill No 3 : Loka round primary school – Latrine block (A)					
1	Provide and allow for carpentry work on minor repair work on 5 doors , replacement of damaged frames and shutter frames : - Ditto but 2"x4" timber - Ditto but 2"x3" timber - Ditto but 4" T hinges - Ditto but 4" tower and barrel bolt - Ditto but pad locks medium size	Meter Meter Set Set Pieces	30 46 8 10 05		
2	Provide and allow for at least 1 coat oil paint on doors	Sqm	16		
3	Provide and allow for at least 2 coats sadolin wall plant, cream , on both internal and external wall surfaces of latrines	Sqm	240		
Subtotal Bill (3) Loka round (A) primary school latrine c/t summery					
Bill No 4 : Loka round primary school – Latrine block (C)					
1	Provide and allow for carpentry work on minor repair work on 5 doors , replacement of damaged frames and shutter frames : - Ditto but 2"x4" timber - Ditto but 2"x3" timber - Ditto but 4" T hinges - Ditto but 4" tower and barrel bolt - Ditto but pad locks medium size	Meter Meter Set Set Pieces	30 46 8 10 05		
	Provide and allow for at least 1 coat oil paint on doors	Sqm	16		

	Provide and allow for at least 2 coats sadolin wall plant, cream , on both internal and external wall surfaces of latrines	Sqm	240		
2	Provide and allow for at least 1 coat oil paint on doors	Sqm	16		
3	Provide and allow for at least 2 coats sadolin wall plant, cream , on both internal and external wall surfaces of latrines	Sqm	240		
Subtotal Bill (4) Loka round (B) primary school latrine c/t summery					
Bill No 5 : Loka round primary school – Latrine block (C)					
1	Provide and allow for carpentry work on minor repair work on 3 doors , replacement of damaged frames and shutter frames : - Ditto but 2"x4" timber - Ditto but 2"x3" timber - Ditto but 4" T hinges - Ditto but 4" tower and barrel bolt - Ditto but pad locks medium size	Meter Meter Set Set Pieces	16 18 6 6 03		
2	Provide and allow for at least 1 coat oil paint on doors	Sqm	12		
3	Provide and allow for at least 2 coats sadolin wall plant, cream , on both internal and external wall surfaces of latrines	Sqm	120		
4	Allow for branding of IR and SIDA logo on walls of 5 latrines blocks as specified	Brands	10		
Subtotal Bill (5) : Loka round (c) primary school c/t summery					
Grand Total : (sub total bill 1+2+3+4+5)					

Note:

- All costs quoted should incorporate cost of materials , labour , equipments , tools , transport , monitoring and supervision and any other related costs .