

Item: BILLS OF QUANTITIES FOR TUKUL CONSTRUCTION

Date:

All prices are in USD

ITEM	DESCRIPTION OF WORK	UNIT	QTY	RATE (USD)	AMOUNT (USD)
A	<u>SUPERSTRUCTURE</u>				
A1	Supply and fix a mild Steel: CHS sections 100 mm X 2 mm: including M15 bolts, & 250 X 250 X 10 mm MS plates etc: as Columns: fixed to mass concrete Slab (See the drawing for Connections details)	LM	6.00		
A2	Supply and fix well treated and polished 100 mm teak pole(2.6 m long) into the CHS pipe (See the drawing for Connections details)	Pcs	12.00		
	SUB-TOTAL-A (SUPER STRUCTURE)				
B	<u>ROOF STRUCTURES</u>				
B1	Supply and fix well treated and polished 100 mm teak pole as:				
B1.1	Tie Beams	LM	25.50		
B1.2	King Post	LM	17.85		
B1.3	Struts & Ties	LM	38.00		
B1.4	Rafters	LM	36.00		
B1.5	Wall Plates	LM	25.80		
B2	Local bamboo as Purlins	LM	645.00		
	SUB-TOTAL-B (ROOF STRUCTURE)				
C	<u>ROOF COVERING</u>				
C1	Supply and laid plastic tarpaulin on the roof structure prior to roof covering	SM	51.77		
C2	Provide Well Cleaned local grass thatching on a plastic tarpaulin as the Roof covering	SM	51.77		
C3	Cast 1:3 Cement/ Sand 40 mm thick Mortar as Ridge Cap	SM	5.30		
C4	Allow for fumigation of the roof covering before prior to handover	SM	51.77		
	SUB-TOTAL-C (ROOF COVERING)				
D	<u>FINISHES</u>				
D1	Allow for painting of Metallic CHS pipes	LS	1.00		
	SUB-TOTAL-D (FINISHES)				
	TOTAL FOR TUKUL CONSTRUCTION				